

ANC is pleased to present the following Display proposal for Spectrum Center for Vomitory Displays per the specifications and pricing below.

LED VIDEO DISPLAYS	PRICING
Large Upper Bowl Vomitory LED Display - 3.28' H x 9.84' W - 3.91mm (Qty 3)	\$27,609
Upper Bowl Vomitory LED Display - 3.28' H x 3.28' W - 3.91mm (Qty 26)	\$79,761
Lower Bowl Vomitory LED Display - 3.28' H x 4.92' W - 3.91mm (Qty 11)	\$50,617
Tunnel Entry LED Display - 3.28' H x 11.48' W - 3.91mm (Qty 3)	\$32,211
(2) Lower Bowl Vomitory and (1) Tunnel LED Display	\$23,008
Lowes Tunnel LED Display - 2.46' H x 36.09' W - 3.91mm (Qty 1)	\$25,309
Structural Materials	\$21,459
Structural Labor and LED Installation	\$97,481
Electrical and Data - Materials and Subcontracting:	\$38,188
Project Management, General Conditions, Travel & Expenses	\$30,916
Submittals, Engineering, and Permits	\$16,875
SUBTOTAL	\$443,434
TAX	\$32,149
GRAND TOTAL	\$475,582

ALTERNATES - ADD TO COST ABOVE	PRICING
Control System Integration	TBD
Primary Power and Data to Displays	TBD
GRAND TOTAL	\$0

TECHNICAL SPECIFICATIONS

DISPLAY NAME	DIMENSIONS	PITCH	RESOLUTION	QTY
Large Upper Bowl Vomitory LED Display	3.28' x 9.84'	3.91mm	256 x 767	3
Upper Bowl Vomitory LED Display	3.28' x 3.28'	3.91mm	256 x 256	26
Lower Bowl Vomitory LED Display	3.28' x 4.92'	3.91mm	256 x 384	11
Tunnel Entry LED Display	3.28' x 11.48'	3.91mm	256 x 895	3
(2) Lower Bowl Vomitory and (1) Tunnel LED Display	3.28' x 8.20'	3.91mm	256 x 639	3
Lowes Tunnel LED Display	2.46' x 36.09'	3.91mm	192 x 2813	1

EXHIBIT B — STATEMENT OF WORK**PHYSICAL INSTALLATION**

ANC assumes all base building structure is to be provided by others or is existing and is of sufficient capacity to support the proposed display systems.

ANC has included removal and disposal of any existing signage and display systems that would be replaced by those systems that are part of this ROM proposal.

ANC assumes reasonable access will be provided to the installation team and any unknown site conditions such as lane closures, site protection, permitting, etc is not currently in this ROM Proposal.

ELECTRICAL & DATA INSTALLATION

ANC assumes primary power feed will be provided by others or is existing, to display location with sufficient amps for ANC proposed display(s); typically 120 or 208v single phase.

ANC assumes all secondary power distribution, which may include breaker panels, disconnects, pathway, etc may be included in this ROM Estimate

ANC assumes all data pathway and cabling is provided by others or is existing.

ANC assumes all data pathways and cables are provided and existing. Any modifications or additional cabling pulls required could result in additional cost. Requires 2 Cat 6 cables to the nearest IDF closet where clear fiber pathway to control exists.

CONTROL SYSTEM

ANC has provided display processors only. No additional control room equipment has been provided as part of this proposal.

ANC will provide appropriate on-site operation and Maintenance Training

GENERAL CONDITIONS

ANC has provided a parts and part repair only warranty, excluding on-site labor, on all products consistent with the factory supplier and/or 3rd party vendor. Warranty Terms and Conditions to be defined.

ANC has not included bonding of any kind.

ANC has not included any tax in the proposal. Any and all sales and use taxes, including, but not limited to, any import or associated duties, fees, tariffs as well other excises and other charges, including without limitation VAT/Sales Tax, ("collectively referred to as Government Charges") now or henceforth levied on any date in connection with the sale of the LED System shall be the full responsibility of the Purchaser. Purchaser shall reimburse ANC for any and all Government Charges ANC may advance on Purchaser's behalf. Purchaser acknowledges that neither ANC nor Purchaser may have advance knowledge of such Government Charges. ANC has excluded any and all taxes from the pricing in the enclosed proposal.

Shipping (Ocean Freight Shipping) included in quote at current shipping pricing. Shipping pricing is subject to change due to continued global impacts of the Covid pandemic. Any increase in costs will be responsibility of Purchaser. Current Ocean Freight timelines are approximately 6 weeks. Current Air Freight timelines are approximately 2 weeks.

The Purchaser acknowledges that amidst the duration of the Covid-19 pandemic ("Pandemic") and thereafter for some undefined period of time, there may be consequences of the Pandemic or adverse market conditions (whether or not sudden or unpredictable) that could render either party's performance. ANC shall not be responsible for any additional compensation hereunder or lost revenues or profits, damages, costs, or overhead incurred by the Purchaser relating to or arising out of (i) breakdowns in commercial negotiations with equipment or parts' suppliers; (ii) delays in shipping or manufacturing or the availability of LED or LCD equipment or parts during the Term (iii) delays in third-party contractor obligations not under ANC's control whose work precedes ANC's obligations hereunder; (iv) Pandemic related closures of facilities or factories or contractors, whether domestic or international, or (v) employee unavailability, staffing shortages, shutdowns, postponements, or cancellations relating to or arising out of the Pandemic, whether due to illness, travel restrictions or Events of Force Majeure.